

# Tech Rider Hotel Cart: Aerial Act

## Hotel Cart Apparatus

### Apparatus Weight:

60 kg

Maximum dynamic weight generating: 240 kg

### Set up:

The Hotel Cart apparatus takes about 45 minutes to set up and 45 minutes to tear down after the presentation. 1 stagehand required to help with the set up for 10 minutes.

### Transport:

The hotel cart apparatus breaks down and fits into 3 separate suitcases to be transported as extra luggage by air (30kg, 20 kg & 20 kg) or in a road-case to be transported via DHL (90 kg total weight). Transport fees are covered by client / organizer / presenter.

### Stage:

The performance area has to be minimum 1.5 meters in width/diameter and needs to be even, clean, and free from dust. Solid hard floor, preferably not carpet. The hotel cart's wheels are lockable.

The ceiling height needs to be 3 meters minimum.

### Rigging:

A winch motor is required for the act. In special cases it may be adapted to a static aerial point: to be discussed with the artist directly.

A professional rigger & winch operator is required. Rigging may only be installed, operated, and inspected by a qualified individual and the artist. The rigger/winch operator may be either provided by the client or the artist at extra cost.

The artist provides the carabiners and the swivel.

### Rigging point:

Height: min 4 meters - no limit upwards

Weight: able to hold a min of 2000kg

## Lighting:

The performance area needs to be lit with a minimum diameter of 2 meters around the Cart, as well the full height of the cart. A front spotlight preferable.

## Sound:

Adequate sound system to be provided by the client. The artist provides the music on a USB stick or via email or airdrop.



